



# MAHANAGAR GAS LIMITED

A Joint Venture of GAIL (India) Ltd., BG Group (U.K.) & Govt. of Maharashtra  
CIN:U40200MH1995PLC088133 E-MAIL ID: info@mahanagargas.com

## LETTER OF INTENT

Date: 26.08.2014

To,  
**M/s. Future Projects**  
Shop No.5 & 6, Happy Home Apartment 1,  
Near Malaika Shanti Park,  
Mira Road (E) – 401 107  
Tel: 022 28119735

**Kind Attn: Mr. Bhanu Singh – Proprietor**

**Subject:** Laying of MP, LP pipe line in DRS 135A, Ambernath – E Area of KDAB Zone

**Reference:** 1) Our Tender No.: MGL/C&P/CA2 PROJECTS/0926/14-15/PM Dated: 5.08.2014  
2) Your Quotation Reference No.: NIL Dated: 20.08.2014

Dear Sir,

With reference to the above, we are pleased to issue this letter of intent for the subject job.

**Contract Period:** The contract shall be valid for period of Eight Months w.e.f 01.09.2014.

**Contract Value:** The estimated value of the contract shall be **Rs. 27,45,040.00** (Rupees Twenty Seven Lacs Forty Five Thousand and Forty only) excluding Taxes.

**Engineer In Charge:** Mr. G.J.P.N Murthy (GM – Projects) shall be the Engineer In Charge for this contract.

The other terms and conditions shall be as per Tender No.: MGL/C&P/CA2 PROJECTS/0926/14-15/PM Dated: 05.08.2014.

Detail Work Order shall be issued after receipt of acceptance of this Letter of Intent (LOI). You are requested to send us a signed copy of this Letter of Intent as a token of your acceptance within seven days of receipt of LOI.

Thanking you,  
**Mahanagar Gas Limited,**

  
**T.L. Sharnagat** 22/8/14  
**Asst. Vice President (Contracts & Procurement, ERP and IT)**

### **Acknowledgement:**

We have received the LOI and confirm acceptance of the same.

Name: \_\_\_\_\_

Signature: \_\_\_\_\_

Company Seal: \_\_\_\_\_



**MAHANAGAR  
GAS**

# MAHANAGAR GAS LIMITED

A Joint Venture of GAIL (India) Ltd., BG Group (U.K.) & Govt. of Maharashtra  
CIN:U40200MH1995PLC088133 E-MAIL ID: info@mahanagargas.com

## WORK ORDER

To,  
Future Projects  
Shop No 5, Happy Home Apts,  
Near Mailaika,  
Shanti Park, Mira Road (E),  
Thane-401107  
Maharashtra, India  
Vendor Code: 203633

WO No :MGL/C&P//4100004147/14/PM  
WO Date :01.09.2014  
RFQ No :MGL/C&P/CA2-PROJECTS/0926/14-15/PM  
RFQ Date :05.08.2014  
Your Quot/Ref No: /NIL DATED: 20.08.2014  
X LOI DATED: 26.08.2014

**Kind Attn:-Mr. Bhanu Singh # Proprietor.**

**Subject :Laying of MP, LP pipe line in DRS 135A, Ambernath # E Area of KDAB Zone**

Dear Sir/Madam

With reference to your offer against our RFQ and all subsequent correspondences (if any) till date and in continuation of our Fax of Intent(if any),we are pleased to award this order highlighting the following salient features:

**Scope of work:**

Laying of Medium Density Poly Ethylene (MDPE) Pipeline for City Gas Distribution Network and Installation of Service Regulator, Regulating Stations for Domestic & Non Domestic customers in Ambernath E Area (KDAB Zone):

The Scope of Work shall be as per Tender No.:MGL/C&P/CA2 PROJECTS/0926/14-15/PM Dated: 05.08.2014.

**Total Contract Value:**The total contract value shall be Rs. 27,45,040.00 (Rupees Twenty Seven Lacs Forty Five Thousand and Forty only) VAT and Service Tax as applicable shall be paid extra by MGL.

**Engineer In-Charge:**

Mr. G.J.P.N Murthy (GM # Projects) shall be the Engineer In Charge for this contract.

**Contract Period :**The contract shall be valid for a period of Eight Months w.e.f 01.09.2014 to 30.04.2015.



Kalina Office, Centrum House, 5th Floor, CST Road, Kalina, Santacruz (East), Mumbai - 400 098.

T +91 6789 2000 | F +91 22 - 2654 1043

An ISO 9001, 14001 & OHSAS 18001 Certified Company



## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

### SCHEDULE OF RATES

Sr.no	Service Code Description	Qty	UOM	Rate ₹	Amount ₹
<b>ITEM 00010 KDAB - MP/LP - AMBERNATH E - LABOUR</b>					
<b>The item covers the following services</b>					
10	1100360 T-Z:SOR1A-80%,It 110	100	M	200.00	20,000.00
Laying of Medium pressure PE pipeline on Municipal/corporation/Private Roads with temporary reinstatement from DRS to upstream of Service Regulator, as per the scope and technical specification detailed in the tender document and MGL code of practice. Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover or U shape RCC block/cover + RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from other utilities. .Separate rate for carrying out Permanent reinstatement ( Labour & material cost )of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. *Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 300 to 600 meters only .; ; Labour cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,*Ø180mm					
20	1100361 T-Z:SOR1A-10%-1,It 110	100	M	25.00	2,500.00
Laying of Medium pressure PE pipeline on Municipal/corporation/Private Roads with temporary reinstatement from DRS to upstream of Service Regulator, as per the scope and technical specification detailed in the tender document and MGL code of practice. Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover or U shape RCC block/cover + RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from other utilities. .Separate rate for carrying out Permanent reinstatement ( Labour & material cost )of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. *Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 300 to 600 meters only .; ; Labour cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,*Ø180mm					
30	1100362 T-Z:SOR1A-10%-2,It 110	100	M	25.00	2,500.00
Laying of Medium pressure PE pipeline on Municipal/corporation/Private Roads with temporary reinstatement from DRS to upstream of Service Regulator, as per the scope and technical specification detailed in the tender document and MGL code of practice. Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover or U shape RCC block/cover + RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from other utilities. .Separate rate for carrying out Permanent reinstatement ( Labour & material cost )of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. *Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 300 to 600 meters only .; ; Labour cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,*Ø180mm					
40	1100366 T-Z:SOR1AA-80%,It 111	50	M	320.00	16,000.00
Laying of Medium pressure PE pipeline on municipal/ corporation as per Appendix III with temporary reinstatement (of Municipal Corporation Roads/private Roads ) across all the road crossings in KPT Area as per the scope and technical specification detailed in the tender document .Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover+ RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance					





## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

from proximity with occupied buildings. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. Separate rate for carrying out Permanent reinstatement ( Labour & Material cost ) of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 25 to 50 meters only . ; Labour cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

50	1100367	50	M	40.00	2,000.00
----	---------	----	---	-------	----------

T-Z:SOR1AA-10%-1,It 111

Laying of Medium pressure PE pipeline on municipal/ corporation as per Appendix III with temporary reinstatement (of Municipal Corporation Roads/private Roads ) across all the road crossings in KPT Area as per the scope and technical specification detailed in the tender document .Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover+ RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from proximity with occupied buildings. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. Separate rate for carrying out Permanent reinstatement ( Labour & Material cost ) of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 25 to 50 meters only . ; Labour cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

60	1100368	50	M	40.00	2,000.00
----	---------	----	---	-------	----------

T-Z:SOR1AA-10%-2,It 111

Laying of Medium pressure PE pipeline on municipal/ corporation as per Appendix III with temporary reinstatement (of Municipal Corporation Roads/private Roads ) across all the road crossings in KPT Area as per the scope and technical specification detailed in the tender document .Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover+ RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from proximity with occupied buildings. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. Separate rate for carrying out Permanent reinstatement ( Labour & Material cost ) of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 25 to 50 meters only . ; Labour cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

70	1100374	50	M	3,128.00	156,400.00
----	---------	----	---	----------	------------

T-Z:SOR1D-A(Pre-Priced)-80%,It 114

For Nallahs: Laying of PE pipe below the drains/culverts/nallahs at least 1000 mm below the bed with protection, as per the scope of work detailed at Chapter Y (1 of 4) & Dwg. No. MGL/ENG/ MP/NLBNL/17 Rev-3 of (Appendix-V).; For nallah having any span; Charges for laying of PE pipe below drains/culverts/nallah having any depth from ground level.

80	1100375	50	M	391.00	19,550.00
----	---------	----	---	--------	-----------

T-Z:SOR1D-B-10%-1,It 114

For nallahs having any depth: Laying of PE pipe below the drains/culverts/nallahs at least 1000 mm below the bed with protection, as per the scope of work detailed at 'Technical requirements & Special Conditions of Contract (SCC)' & Dwg. No. MGL/ENG/ MP/NLBNL/17 Rev-3 of (Appendix-V).; For nallah having any span; Charges for laying of PE pipe below drains/culverts/nallah having any depth from ground level.

90	1100376	50	M	391.00	19,550.00
----	---------	----	---	--------	-----------

T-Z:SOR1D-B-10%-2,It 114

For nallahs having any depth: Laying of PE pipe below the drains/culverts/nallahs at least 1000 mm below the bed with protection, as per the scope of work detailed at 'Technical requirements & Special Conditions of Contract (SCC)' & Dwg. No. MGL/ENG/ MP/NLBNL/17 Rev-3 of (Appendix-V).; For nallah having any span ; Charges for laying of PE pipe below drains/culverts/nallah





## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

having any depth from ground level.

100	1100380 T-Z:SOR1G-100%,It 119	80	M3	2,600.00	208,000.00
Breaking of hard rock as per the details at Clause No. 1.14 & 2.4 of 'Technical requirements & Special Conditions of Contract (SCC).'; ; Breaking of hard rock					
110	1100381 T-Z:SOR1SA(Pre-Priced)-100%,It 120	200	M	20.00	4,000.00
Compliance to Health, Safety, Environment (HSE) as per the Clause No. 1.37 detailed in 'Technical requirements & Special Conditions of Contract (SCC)'; ; Charges for Compliance of HSE					
120	1100382 T-Z:SOR1SB(Pre-Priced)-100%,It 121	400	M	14.00	5,600.00
Separate rate for providing Plastic barricading at MP pipeline laying work as per the Clause No 1.38; ; Providing barricading					
130	1100383 T-Z:SOR2A-80%,It 210	4,000	M	200.00	800,000.00
PE pipe laying for low pressure network in new area / buildings area as per the scope and technical specification detailed at Clause No. 2.1 to 2.23 of Chapter Y of . Separate rate for carrying out Permanent reinstatement of Private road shall be paid under SOR 1B.; ; Labour cost for laying PE pipe of Ø 20/32/63 mm					
140	1100384 T-Z:SOR2A-10%-1,It 210	4,000	M	25.00	100,000.00
PE pipe laying for low pressure network in new area / buildings area as per the scope and technical specification detailed at Clause No. 2.1 to 2.23 of Chapter Y of . Separate rate for carrying out Permanent reinstatement of Private road shall be paid under SOR 1B.; ; Labour cost for laying PE pipe of Ø 20/32/63 mm					
150	1100385 T-Z:SOR2A-10%-2,It 210	4,000	M	25.00	100,000.00
PE pipe laying for low pressure network in new area / buildings area as per the scope and technical specification detailed at Clause No. 2.1 to 2.23 of Chapter Y of . Separate rate for carrying out Permanent reinstatement of Private road shall be paid under SOR 1B.; ; Labour cost for laying PE pipe of Ø 20/32/63 mm					
160	1100389 T-Z:SOR2AS(Pre-Priced)-100%-,It 211	4,000	M	12.00	48,000.00
Compliance to Health, Safety, Environment (HSE) as per the scope of work detailed at clause 2.24 .; ; Charges for Compliance of HSE					
170	1100390 T-Z:SOR2AB(Pre-Priced)-100%,It 212	8,000	M	5.00	40,000.00
Separate rate for providing cordoning at LP pipeline laying work as per the clause 2.24 ; ; CORDONING					
180	1100394 T-Z:SOR3-100%,It 310	50	EA	500.00	25,000.00
Installation Of Service Regulator Module as per the scope and technical specification detailed at Clause No. 3.0, 3.1 to 3.9 of Chapter Y (2 of 4)of , with Compliance to Health, Safety, Environment (HSE) as per the Clause No. 3.10 & 3.11.; ; Labour cost for installation of SR module					
190	1100396 T-Z:SOR4(Pre-Priced)-100%,It 410	10	EA	500.00	5,000.00





## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

Rates For providing Manpower , skilled , semi skilled & skilled as per the scope detailed in tender document.; ; Man day rates for providing Technician (8 Working hrs.)

200	1100397	10	EA	480.00	4,800.00
	T-Z:SOR4(Pre-Priced)-100%,It 411				

Rates For providing Manpower , skilled , semi skilled & skilled as per the scope detailed in tender document.; ; Man day rates for providing Technicians Assistant / Labour (8 working hrs.)

210	1100398	10	EA	500.00	5,000.00
	T-Z:SOR4(Pre-Priced)-100%,It 412				

Rates For providing Manpower , skilled , semi skilled & skilled as per the scope detailed in tender document.; ; Man day rates for providing Supervisor (8 working hrs.)

220	1100399	10	EA	450.00	4,500.00
	T-Z:SOR4(Pre-Priced)-100%,It 413				

Rates For providing Manpower , skilled , semi skilled & skilled as per the scope detailed in tender document.; ; Man day rates for providing unskilled labor (8 working hrs.)

230	1100400	20	EA	148.00	2,960.00
	T-Z:SOR5-100%,It 510				

Miscellaneous Incomplete Jobs; ; Labour charges for fixing of only crimping, as per clause 5.1

240	1100401	100	EA	125.00	12,500.00
	T-Z:SOR5-100%,It 511				

Miscellaneous Incomplete Jobs; ; Labour charges for fixing of crimp guard, as per clause 5.2

250	1100402	100	M	175.00	17,500.00
	T-Z:SOR5-100%,It 512				

Miscellaneous Incomplete Jobs; ; Labour charges for reinstatement inside the premises of society, as per clause no 5.3

260	1100404	20	EA	634.00	12,680.00
	T-Z:SOR5-100%,It 515				

Miscellaneous Incomplete Jobs; ; Labour charges for PE electro-fusion joints (up to 180 mm) as per clause 515

270	1100406	1,000	M	39.00	39,000.00
	T-Z:SOR5-100%,It 517				

Miscellaneous Incomplete Jobs; ; Labour charges for Rectification , Testing & commissioning of 100 mbar PE pipeline up to dia 63 mm, as per clause no 5.8

### ITEM 00020 KDAB- MP/LP - AMBERNATH E - MATERIAL

The item covers the following services

10	1100363	100	M	200.00	20,000.00
	T-Z:SOR1A-80%,It 110.a				

Laying of Medium pressure PE pipeline on Municipal/corporation/Private Roads with temporary reinstatement from DRS to upstream of Service Regulator, as per the scope and technical specification detailed in the tender document and MGL code of practice. Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover or U shape RCC block/cover + RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from other utilities. .Separate rate for carrying out Permanent reinstatement ( Labour & material cost )of Private road shall be paid under SOR 1B. RCC Tiles ,U Block, cover & Bottom slab shall be supplied by MGL. \*Total





## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 300 to 600 meters only ; ;  
Material cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

20	1100364	100	M	25.00	2,500.00
T-Z:SOR1A-10%-1,It 110.a					

Laying of Medium pressure PE pipeline on Municipal/corporation/Private Roads with temporary reinstatement from DRS to upstream of Service Regulator, as per the scope and technical specification detailed in the tender document and MGL code of practice. Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover or U shape RCC block/cover + RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from other utilities. .Separate rate for carrying out Permanent reinstatement ( Labour & material cost )of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total

Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 300 to 600 meters only ; ;  
Material cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

30	1100365	100	M	25.00	2,500.00
T-Z:SOR1A-10%-2,It 110.a					

Laying of Medium pressure PE pipeline on Municipal/corporation/Private Roads with temporary reinstatement from DRS to upstream of Service Regulator, as per the scope and technical specification detailed in the tender document and MGL code of practice. Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover or U shape RCC block/cover + RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from other utilities. .Separate rate for carrying out Permanent reinstatement ( Labour & material cost )of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total

Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 300 to 600 meters only ; ;  
Material cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

40	1100369	50	M	320.00	16,000.00
T-Z:SOR1AA-80%,It 111.a					

Laying of Medium pressure PE pipeline on municipal/ corporation as per Appendix III with temporary reinstatement (of Municipal Corporation Roads/private Roads ) across all the road crossings in KPT Area as per the scope and technical specification detailed in the tender document .Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover+ RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from proximity with occupied buildings. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL.Separate rate for carrying out Permanent reinstatement ( Labour & Material cost ) of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total

Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 25 to 50 meters only . ; ; Material cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm ,\*Ø180mm

50	1100370	50	M	40.00	2,000.00
T-Z:SOR1AA-10%-1,It 111.a					

Laying of Medium pressure PE pipeline on municipal/ corporation as per Appendix III with temporary reinstatement (of Municipal Corporation Roads/private Roads ) across all the road crossings in KPT Area as per the scope and technical specification detailed in the tender document .Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover+ RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from proximity with occupied buildings. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL.Separate rate for carrying out Permanent reinstatement ( Labour & Material cost ) of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total

Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 25 to 50 meters only . ; ; Material cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm





## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

,\*Ø180mm  
60 1100371 50 M 40.00 2,000.00  
T-Z:SOR1AA-10%-2,It 111.a

Laying of Medium pressure PE pipeline on municipal/ corporation as per Appendix III with temporary reinstatement (of Municipal Corporation Roads/private Roads ) across all the road crossings in KPT Area as per the scope and technical specification detailed in the tender document .Laying of Medium pressure PE pipeline through RCC enclosure (U shape RCC block/cover+ RCC bottom slab) as per scope work and technical specification detailed in tender document and MGL code of Practice for maintaining clearance from proximity with occupied buildings. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL.Separate rate for carrying out Permanent reinstatement ( Labour & Material cost ) of Private road shall be paid under SOR 1B. RCC Tiles ,U BLock , cover & Bottom slab shall be supplied by MGL. \*Total Quantity of Ø180 mm pipeline Laying per zone during the contract period would be in the range of 25 to 50 meters only . ; ; Material cost for laying PE pipe of Ø63 mm, Ø90 mm & Ø125 mm

,\*Ø180mm  
70 1100386 4,000 M 200.00 800,000.00  
T-Z:SOR2A-80%,It 210.a

PE pipe laying for low pressure network in new area / buildings area as per the scope and technical specification detailed at Clause No. 2.1 to 2.23 of Chapter Y of . Separate rate for carrying out Permanent reinstatement of Private road shall be paid under SOR 1B.; ; Material cost for laying PE pipe of Ø 20/32/63 mm

80 1100387 4,000 M 25.00 100,000.00  
T-Z:SOR2A-10%-1,It 210.a

PE pipe laying for low pressure network in new area / buildings area as per the scope and technical specification detailed at Clause No. 2.1 to 2.23 of Chapter Y of . Separate rate for carrying out Permanent reinstatement of Private road shall be paid under SOR 1B.; ; Material cost for laying PE pipe of Ø 20/32/63 mm

90 1100388 4,000 M 25.00 100,000.00  
T-Z:SOR2A-10%-2,It 210.a

PE pipe laying for low pressure network in new area / buildings area as per the scope and technical specification detailed at Clause No. 2.1 to 2.23 of Chapter Y of . Separate rate for carrying out Permanent reinstatement of Private road shall be paid under SOR 1B.; ; Material cost for laying PE pipe of Ø 20/32/63 mm

100 1100395 50 EA 500.00 25,000.00  
T-Z:SOR3-100%,It 310.a

Installation Of Service Regulator Module as per the scope and technical specification detailed at Clause No. 3.0, 3.1 to 3.9 of Chapter Y (2 of 4)of , with Compliance to Health, Safety, Environment (HSE) as per the Clause No. 3.10 & 3.11.; ; Material cost for installation of SR module

**Total Order Value: ₹2,745,040.00**

**TWENTY SEVEN LAKH FORTY FIVE THOUSAND FORTY RUPEES ONLY**

Tax details for item(s) 00020 = Nil ED,VAT- 5%-ND

Tax details for item(s) 00010 = ST12.36%-100%ND(MGL50L&Ven50L)

**The total contract value shall be Rs. 27,45,040.00 (Rupees Twenty Seven Lacs Forty Five Thousand and Forty only) VAT and Service Tax as applicable shall be paid extra by MGL.**

### Header text :

KDAB ZONE - DRS 135A, Ambernath # E Area

**Performance Bank Guarantee/SD**

Security Deposit:

Security Deposit for contract performance in the form of Bank Guarantee as per proforma at (Appendix -





## WORK ORDER(Cont.)

Vendor Code: 203633  
Vendor Name:  
Future Projects

WO No: MGL/C&P//4100004147/14/PM  
WO Date: 01.09.2014

PBG) or DD in favour of Mahanagar Gas Limited, payable at Mumbai shall be submitted. The security deposit shall be for 10% of contract value (excluding Taxes & Duties), valid till the contractual completion time plus 12 months. The Security deposit shall be submitted within 15 days from the date of issue of Letter of intent/Work order whichever is earlier. The Security Deposit for performance, if submitted in the form of BG, shall be from a Nationalized Bank /Scheduled Bank / Cooperative Schedule Bank / Multi National Bank / Reputed Foreign Bank only. No interest on security deposit shall be paid.

Alternatively, Service Provider may submit BG towards security deposit for 5% of contract value and balance 5% shall be deducted from their running bill @ 10% till the amount becomes 5% of the contract value.

### INDEMNITY BOND:

You shall submit the Indemnity Bond as per proforma at (Appendix - IB) against free issue of material / goods supplied to the contractor by MGL, which is equivalent to the value of Rs. 25 Lacs.

### General Condition of Contract

The General Condition of Contract shall be as per Tender No.: MGL/C&P/CA2 PROJECTS/0926/14-15/PM Dated: 05.08.2014.

### Special Conditions of Contract

The Special Condition of Contract shall be as per Tender No.: MGL/C&P/CA2 PROJECTS/0926/14-15/PM Dated: 05.08.2014.

### Terms of payment

Payments Terms shall be as per Tender No.:MGL/C&P/CA2 PROJECTS/0926/14-15/PM Dated: 05.08.2014.

### Other contractual stipulations

You shall comply with all the necessary statutory formalities required for the work. The agency should take care of PF, ESIC, Accident insurance & other incidental expenses and provision of Labour Act as applicable. You may collect form V From GM- (HR & ADMIN) for taking necessary actions at your end (i.e. for registration with Labour Commissioner).

### AHR/ALR Items

As per Tender Terms Following Items are identified as AHR items and the Revised rates for the same beyond Tender Quantity (As mentioned in SOR above) shall be as under:

Item No.	SOR No.	Tender Qty	Revised Rate in Rs./Unit
1	3 310	50 Nos.	200.00
2	3 310.a	50 Nos.	400.00





## WORK ORDER(Cont.)

Vendor Code: 203633

Vendor Name:

Future Projects

WO No: MGL/C&P//4100004147/14/PM


WO Date: 01.09.2014

---

Please send us a copy of this Work order duly signed as token of acceptance

Yours Truly,

for MAHANAGAR GAS LTD.

  
(Authorized Signatory)

**T.L Sharnagat**

**Asst. Vice President (Contracts & Procurement, ERP and IT)**



# MAHANAGAR GAS LTD.

## DOCUMENTS CHECK LIST FOR SERVICE PROVIDER

(Service providers / Contractors shall ensure the following documents are enclosed while submitting the bills / invoice to the Engineer In-charge)

WO No.:

WO Date:

We M/s \_\_\_\_\_ hereby confirm that we have submitted following set of documents along with the bills / invoice to the Engineer In-charge.

Sr.No.	Documents	Submitted	Not Applicable (NA)
1	Original Tax Invoice (with Service No., Service Tax No., Service Tax Category and Service Tax breakup, VAT declaration as per Maharashtra Value Added Tax Act 2002, if VAT is applicable)		
2	Test Certificate and Reports / Measurement Sheet / Drawings or any other mentioned in the Tender.		
3	No Dues / No Claim Certificate (to be submitted while submitting Last Bill / Invoice of the contract).		

(Please tick all sections)

Place:  
Date:

Signature of Service Provider with the seal of the firm

Name and Designation & Contact No  
of Authorized Person

### Billing address for Tax Invoice:

(Engineer In-charge)  
Mahanagar Gas Ltd.,  
City Gate Station,  
Opp. Anik Bus Depot,  
Near Everard Nagar,  
Sion (East),  
Mumbai - 400022.  
Tel : 022 - 24012451  
Fax: 022 - 24010080

Or

Mahanagar Gas Ltd.,  
MGL House, Block No.G-33,  
Opp. ICICI Tower,  
Bandra Kurla Complex,  
Bandra (East),  
Mumbai-400 051.  
Tel : 022 - 66785000  
Fax: 022 - 26541046/26540092

### MGL's Statutory Details

VAT Tin No. :27390000364V  
CST Tin No. :27390000364C  
Excise No. :AABCM4640GXM001, Range - 03, Division - Chembur -I,  
Commissionerate - Mumbai - II

